

**Construction of 4(four) Super Speciality Hospitals under BRGF  
at Metiaburz and Kakdwip in South 24 Parganas, at Sagardighi in  
Murshidabad and at Bolpur in Birbhum (Package 1)**

## **TENDER DOCUMENTS**

**Addendum No.3 to Tender Document  
Dated 23.12.2013**

**HOOGLY RIVER BRIDGE COMMISSIONERS**

**(A Statutory Organisation under Government of West Bengal)**

**TRANSPORT DEPARTMENT**

**MUNSHI PREMCHAND SARANI**

**( ST. GEORGE'S GATE ROAD )**

**KOLKATA – 700 021**

**December 2013**

**Construction of 4(four) Super Speciality Hospitals under BRGF  
at Metiaburz and Kakdwip in South 24 Parganas, at Sagardighi in  
Murshidabad and at Bolpur in Birbhum (Package 1)**

**TENDER DOCUMENTS**

**Addendum No.3 to Tender Document  
Dated 23.12.2013**

**CONTENTS**

Addendum No.3 to Tender Document consists of the following document:

- List of corrigenda
- Page No.74 of Vol. IV, Bill of Quantities

## Addendum No.3 to Tender Document

### List of Corrigenda

In pursuance with Clause 9 of Section 2 of Volume I (i.e. Instruction to Bidders), the following modifications are made to the Tender Documents:

SI. No.	Location in Tender documents	Modifications
<b>BOOK – 2, Volume IV, Bill of Quantities</b>		
1.	Page 74 of BOQ	<b>The existing Page No.74 is deleted and substituted by a new Page No.74 as Addendum No.3 to Tender Document, dt. 23.12.13 (marked on the header).</b>

Sl.No	Technical Specification Clause No.	Description of work	Unit	Quantity	Rate (Rs.)		Amount (Rs)
					In Figure	In Words	
B		Sewage Treatment Plant					
		Design, Supplying, Installing, Testing & Commissioning of Sewage Treatment Plant capacity 170KLD. The plant proposed shall be 170 kld with a main pump room. The plant is proposed to be installed in the Under-ground from the pump room itself for future maintenance. Opening shall be provided on above for this purpose, for the following :	Set	4			
		Nature of effluent - Domestic Sewage from Toilet use and kitchen waste, washing waste water.					
		Daily average flow - 170 Cum / Day					
		pH - 6.5 - 8.5					
		BOD5 - upto 250-450 Mg/L					
		S. Solids - 250 - 400 Mg/L					
		COD - upto 450-600 Mg/L					
		Oil & Grease - 50 Mg / L					
		Effluent discharge standard after treatment					
		pH - 6.5 - 8.5					
		BOD5 - Less than 30 Mg/L					
		S. Solids - Less than 10 Mg/L					
		COD - Less than 100 Mg/L					
		Oil & Grease - Nil					
		Sewage treatment plant shall include the following items:					
		Screen Chamber					
		Sewage equalization tank/sump					
		MBBR(FAB) Tanks					
		Settling/ Clarifier Tank					
		Clear Water tank					
		Softener Feed PUMPS					
		Soft Water tank					
		Sludge Holding Tank					
		Plant Room Sump					
		Filtration through MGF & ACF, softner					
		Air Blowers, Pumps & equipment, filter press.					
		Piping, valves etc					
		Electrical Panel & Cabling					
		Common plant room adjacent to STP.					
		All piping, valves & level indicator/controller etc. within plant room.					
a		Supply, installation, testing & commissioning of 2 Nos Stainless Steel Perforated Screen with suitable lifting arrangement (size 600 mm wide x 1200 mm high approx)	Set	4			
b		Supply, installation, testing & commissioning of electronic type level indicator and controller for automatic operation of the system with high/low level alarm complete with auxiliary NO/NC contacts.	Set	4			